



HOT SEAL ALL EDGES
W/12" WIDE PG 64S-22

* PER PENNDOT BUT
NOT LESS THAN
SHOWN ON PLANS

SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING
COURSE, PG 64S-22, 3 TO < 30 MILLION ESALS, 9.5 MM
MIX, 1.5" DEPTH, MATCH EXISTING SRL OR GREATER

SUPERPAVE ASPHALT MIXTURE DESIGN,
BINDER COURSE, PG 64S-22, 3 TO < 30
MILLION ESALS, 19.0 MM MIX, 2.5" DEPTH

SUPERPAVE ASPHALT MIXTURE DESIGN,
BASE COURSE, PG 64S-22, 3 TO < 30
MILLION ESALS, 25.0 MM MIX, 5" DEPTH

2A OR 2RC AS SPECIFIED.

1' SAW CUT, TYP.

COMMENTS

1. EXPOSED VERTICAL AND HORIZONTAL SURFACES SHALL BE PREPARED AS PER PUB. 408, SECTION 413.3(g).
2. MINIMUM 1' PAVEMENT CUTBACK, EXCAVATE OLD AND TEMPORARY MATERIAL. RECOMPACT SUB-GRADE. TACK COAT ALL VERTICAL EDGES. INSTALL ONLY BASE COURSE AND BINDER COURSE IN ONE DAY, OR AS DIRECTED.
3. PERMANENT RESTORATION TO BE MINIMUM 90 DAYS UNLESS FLOWABLE FILL IS USED, OR AS DIRECTED.

NOTES:

1. MATCH EXISTING DEPTHS IF GREATER.
2. RESTORE PAVEMENT MARKINGS WITH APPROVED THERMOPLASTIC PAINT.

PENNDOT FLEXIBLE TRENCH RESTORATION
NOT TO SCALE

REVISED 5/13/2025



PENNONI ASSOCIATES INC.
150 Ridge Road, Suite 2
Sellersville, PA 18960
T 215-257-5711 F 215-257-5766

FLEXIBLE PAVEMENT RESTORATION
PREPARED FOR:
PERKASIE REGIONAL AUTHORITY

DESIGNED BY:	JAR
CHECKED BY:	SRT
DATE:	5/21/12
DRAWING NO.	PRA-S022B

MAUTHORITY CLIENTS/PERKASIE/SANITARY DETAILS/PRA SANITARY DETAILS 2025 DWG
 PLOTTED: 7/19/2025 10:07:53 AM BY: TINA CARTER PLOTSTYLE: PENNONI.NCS SIB: PROJECT STATUS: ---